

BORDER REVISED 11/01/16

CONDUIT AND WIRING SCHEDULE (FURNISH AND INSTALL CONDUIT AND WIRES)																																								
CONDUIT RUN NUMBER		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
CONDUIT SIZE (INCH)		2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	3	2	2	2	2	2	2	2	2	2	2	2	2	2	2	3	2	2	2	2	2	2	2	
C			GRS	GRS	GRS				GRS	GRS	GRS			GRS	GRS	GRS						GRS	GRS	GRS		GRS	GRS	GRS							HDPE	HDPE				
NOTES				SP	SP		A	A		SP	SP		EX			SP		SP					SP	SP	A		SP	SP		EX			SP	SP		SP	SP	B	B	B
	VEHICLE SIGNAL 14	3	3						3					3			3																							
	VEHICLE SIGNAL 64	3	3						3					3			3																							
	VEHICLE SIGNAL 61	3	3						3					3			3																							
	PED SIGNAL 49	2	2						2					2			2																							
	APS PPB FOR XING 3RD ST ON POLE 8	2	2						2					2			2																							
	APS PPB FOR XING 3RD ST ON POLE 5					2			2					2			2																						2	
	TRANSIT SIGNAL 447 167						2		2					2			2																						2	
	TRANSIT SIGNAL 453 143						2		2					2			2																						2	
	TRANSIT SIGNAL 137							2	2					2			2																						2	
	TRANSIT SIGNAL 463 173							2	2					2			2																						2	
	VEHICLE SIGNAL 12											3			3		3																							
	VEHICLE SIGNAL 25											3			3		3																							
	PED SIGNAL 29											2			2		2																							
	APS PPB FOR XING 3RD ST ON POLE 4											2			2		2																							
	PED SIGNAL 48												2		2		2																							
	APS PPB FOR XING SOUTH ON POLE 3												2		2		2																							
	VEHICLE SIGNAL 84																	3	3			3				3					3									
	VEHICLE SIGNAL 65																				3	3				3						3								
	VEHICLE SIGNAL 81																				3	3				3						3								
	PED SIGNAL 88																				2	2				2						2								
	APS PPB FOR XING 3RD ST ON POLE 10																				2	2				2						2								
	TRANSIT SIGNAL 443 163																								2	2							2							
	TRANSIT SIGNAL 457 147																								2	2							2							
	TRANSIT SIGNAL 133																								2	2							2							
	TRANSIT SIGNAL 467 177																								2	2							2							
	VEHICLE SIGNAL 24																												3				3							
	VEHICLE SIGNAL 21																												3				3							
	PED SIGNAL 28																												2				2							
	APS PPB FOR XING 3RD ST ON POLE 1																												2				2							
	VEHICLE SIGNAL 85																													3	3		3							
	PED SIGNAL 89																													2	2		2							
	APS PPB FOR XING SOUTH ON POLE 2																													2	2		2							
	#14 NEUTRAL	4					1	1				2	1						1		2					2				3	2									
	#14 SPARE		3						6					6	3		9					3				6						9						3		
	TOTAL #14 WIRES	17	16			2	5	5	29			12	5	29	17		46		4	3	12	16			10	27			13	9	7	47						13		
	#10 WIRES NEUTRAL		1						2					2	1		3			1		2				3					1	4								
	#8 WIRES (120 V SERVICE)																																							

SHEET NOTES:

A FOR TRANSIT SIGNALS, SEE SG-SERIES PLANS FOR CONDUIT WORKS.

B FOR TRANSIT SIGNAL USE.

C ALL NEW CONDUITS SHALL BE PVC SCHEDULE 80, UNLESS OTHERWISE NOTED.

NO.

DATE

DESCRIPTION

REVISED

CHECKED

APPROVED

REVISIONS

DESIGNED

DRAWN

CHECKED

REVIEWED

RECOMMENDED

APPROVED

DATE

CERYL L. CHAVEZ

No. C56718

Exp. 6/30/19

CIVIL

STATE OF CALIFORNIA

DESIGNED

DRAWN

CHECKED

REVIEWED

RECOMMENDED

APPROVED

DATE

F. Mohamoud

REGISTERED PROFESSIONAL ENGINEER

No. E16033

ELECTRICAL

STATE OF CALIFORNIA

SEAL OF THE CITY AND COUNTY OF SAN FRANCISCO

CITY AND COUNTY OF SAN FRANCISCO

MUNICIPAL TRANSPORTATION AGENCY

APPROVED

for the DIRECTOR OF TRANSPORTATION

MUNI METRO SYSTEM

UCSF PLATFORM AND TRACK IMPROVEMENT PROJECT

CONDUIT & WIRING SCHEDULE

3RD STREET AND ~~SOUTH STREET~~

WARRIORS WAY

CONTRACT

1305

DRAWING

CL-31237

ET-1.1

ET-2.2

REVISION

0