

CONDUIT AND WIRING SCHEDULE (FURNISH AND INSTALL CONDUIT AND WIRES)																																																		
CONDUIT RUN NUMBER		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40A	40B	41	42	43	44	45			
CONDUIT SIZE (INCH)		2	1	2	2	2	2	2	2	2	2	2	2	3	2	2	1	2	2	2	2	2	2	2	1	2	3	2	2	3	2	1	1	2	2	2	2	2	2	2	3	3	2	2	2	2	2			
NOTES						SP			GRS			GRS				GRS			SP				SP			GRS		SP	GRS										GRS					GRS	GRS	GRS				
	VEHICLE SIGNAL 24	3			3					3			3	3																									N											
	VEHICLE SIGNAL 21	3			3					3			3	3																									O											
	PED SIGNAL 28	2			2					2			2	2																																				
	APS PPB XING ALEMANY ON POLE 2		2		2					2			2	2																										U										
	VEHICLE SIGNAL 42			3	3					3			3	3																																				
	PED SIGNAL 89			2	2					2			2	2																																				
	APS PPB XING NIAGARA ON POLE 3			2	2					2			2	2																																				
	VEHICLE SIGNAL 41						3			3			3	3																																				
	PED SIGNAL 48						2			2			2	2																																				
	APS PPB XING NIAGARA ON POLE 4						2			2			2	2																																				
	PED SIGNAL 29							2		2			2	2																																				
	APS PPB XING ALEMANY ON POLE 5							2		2			2	2																																				
	VEHICLE SIGNAL 63										3		3	3																																				
	APS PPB XING ALEMANY ON POLE 6										2		2	2																																				
	VEHICLE SIGNAL 23															3		3				3					3																							
	APS PPB XING ALEMANY ON POLE 12																2	2				2					2																							
	VEHICLE SIGNAL 65																					3		3			3																							
	VEHICLE SIGNAL 22																					3		3			3																							
	PED SIGNAL 69																					2		2			2																							
	APS PPB XING ALEMANY ON POLE 11																					2		2			2																							
	VEHICLE SIGNAL 81																										3		3																					
	PED SIGNAL 88																																																	
	APS PPB XING NIAGARA ON POLE 10																																																	
	VEHICLE SIGNAL 82																																																	
	PED SIGNAL 49																																																	
	APS PPB XING NIAGARA ON POLE 9																																																	
	APS PPB XING ALEMANY ON POLE 8																																																	

SHEET NOTES:

1 4-2" HDPE SCHEDULE 80 CONDUIT WITH 3/8" PULL TAPE IN EACH CONDUIT. IN ONE OF THE EMPTY CONDUITS, THERE ARE TWO #8 AWG STRANDED COPPER LOCATING WIRES (ONE WITH BLACK INSULATION AND THE OTHER WITH WHITE INSULATION).

[illegible]